



TEST REPORT

N° 439A_15

The test results can be applied only to the tested objects.


The report cannot be reproduced partially without permission from ELCON MEGARAD SpA



Prepared by: Eng. P. Marino

Approved by: Mr. F. Portas

A blue ink signature is written over a circular stamp. The stamp contains the text "elcon megarad s.p.a." and "UFFICIO TECNICO" below it. The signature appears to be "F. Portas".

	H.V. LABORATORY	Report n°: 439A/15
		Date: 03/02/2015
		Page: 2/8

Report n°: 439A/15		Date: 03/02/2015
Customer: Elcon Megarad SpA		
Place: ELCON MEGARAD S.p.a. - H.V. Laboratory – Via Nazionale 110 Arcella (AV) ITALY		
Testing date: 07/01/2015 ÷ 02/02/2015		
OBJECTS:	Type: ELCOTERM TIS - 5282/ E-R ELCOTERM GLS - 5285/ E- R ELCOTERM TES - 5284/ E- R	Drawing: 910/E 916/E 912/E
DESCRIPTION: SINGLE CORE HEAT SHRINKABLE INDOOR TERMINATION SINGLE CORE HEAT SHRINKABLE JOINT SINGLE CORE HEAT SHRINKABLE OUTDOOR TERMINATION		
VOLTAGE: $U_0/U = 26/45\text{kV}$ (U_{\max} 52kV)		
CABLE & SECTION: 1x240 sqmm AL/XLPE/PVC		
REFERENCE STANDARD: IEC 60840 TAB. C.1		
TEST METHODS: IEC (60811-1-1; 60230; 60840; 60885-3)		
RESULTS: The tested objects are in accordance with the reference Standard.		
ELCON MEGARAD H.V. Lab. Responsible:	Eng. P. Marino	 Elcon Megarad S.p.A. UFFICIO TECNICO
Test Operator:	Mr. F. Lombardo	
Technical Director:	Mr. F. Portas	
This report consist of: 8 Pages		

Elcon Megarad Operator 	Elcon Megarad H.V. Lab. Responsible 
--	---

IL RESPONSABILE

COMPONENTS CONTROL ACCESSORIES ASSEMBLING CONTROL

- N° 2 MEDIUM VOLTAGE SINGLE CORE CABLE LINE, EM-52/1 AND EM-52/2 HAVE BEEN ASSEMBLED BY ELCON MEGARAD OPERATOR, WITH 3 ACCESSORIES ACCORDING TO THE INSTALLATION INSTRUCTION AS FOLLOWS:


COMPOSITION OF THE SINGLE CORE CABLE LINE

Date: 07/01/15

Line	Cables	Indoor Termination	Joint	Outdoor Termination
EM-52/1	1x240 sqmm AL/XLPE/PVC	(1) ELCOTERM TIS 5282/E-R	(2) ELCOTERM GLS 5285/E-R	(3) ELCOTERM TES 5284/E-R
EM-52/2	1x240 sqmm AL/XLPE/PVC	(1) ELCOTERM TIS 5282/E-R	(2) ELCOTERM GLS 5285/E-R	(3) ELCOTERM TES 5284/E-R

Line Drawing:

(indicative scheme of the 2 single core cable line 26/45 (52)kV)



Elcon Megarad
Operator

Lombardo

Elcon Megarad
H.V. Lab. Responsible



M. RESPONSABILE

TEST SEQUENCE

IEC 60840 TAB. 4

N°	TEST	TEST REQUIREMENTS	Test Voltage [kV] 26/45(52) kV
01	Measurement of thickness of cable insulation	According to clause 10.6	--
02	Partial discharge at ambient temperature	Max 5pC at 1,5 U ₀	39
03	Electrical heat cycling in air	20 cycles at 2U ₀	52
04	Partial discharge at ambient temperature	Max 5pC at 1,5U ₀	39
05	Impulse voltage at ambient temperature	10 impulses of each polarity	250 peak
06	A.C. voltage dry withstand	30 minutes at 2,5U ₀	65
07	Examination	For information only	---
Notes			


Elcon Megarad
Operator*Lombardo***Elcon Megarad**
H.V. Lab. Responsible

IL RESPONSABILE

	H.V. LABORATORY	Report n°: 439A/15 Date: 03/02/2015 Page: 5/8

TEST 01	Measurement of thickness of cable insulation		
OK	LINE:	EM-52/1 - EM-52/2	
	The measurement of thickness of cable insulation is compliant with IEC 60840 , clause 10.6.		Date: 07/01/2015

TEST 02	Partial discharge at ambient temperature Max 5pC at 1,5U ₀				
OK	Applied Voltage:	39kV*		45,5kV**	
		EM-52/1	EM-52/1	EM-52/2	EM-52/2
	Partial discharge level [pC]	0,5	1,0	2,0	1,5
	RESULT:	Partial discharge measurement, referring to 2 steps above mentioned is always less than the maximum required.			
	Note: The PD measurement has been performed on each single cable at 25°C. The TETTEX PD measurement bridge has been calibrated to 10pC. * = measurement at 1,5U ₀ ** = measurement at 1,75U ₀			Date: 07/01/2015	


Elcon Megarad Operator <i>Lombardo</i>	Elcon Megarad H.V. Lab. Responsible 
---	--

IL RESPONSABILE


	H.V. LABORATORY	Report n°: 439A/15 Date: 03/02/2015 Page: 6/8

TEST 03	Electrical heat cycling in air 20 cycles at $2U_0$			
OK	Line:	EM-52/1 - EM-52/2		
	Applied Voltage:	52kV		
	Loading Current	Approx 595 A		
	Number of cycles:	20		
	RESULT:	No flashovers or breakdowns		
	The heating shall be applied for at least 8 h , the conductor temperature shall be maintained within the stated temperature limits for at least 2 h of each heating period and followed by at least 16 h of natural cooling to a conductor temperature less than or equal to ambient temperature.		Date Start : 08/01/2015 Date End : 29/01/2015	

TEST 04	Partial discharge at ambient temperature Max 5pC at 1,5U ₀				
OK	Applied Voltage:	39kV*		45,5kV**	
		EM-52/1	EM-52/1	EM-52/2	EM-52/2
	Partial discharge level [pC]	0,5	1,5	1,5	2,0
	RESULT:	Partial discharge measurement, referring to 2 steps above mentioned is always less than the maximum required.			
	Note: The PD measurement has been performed on each single cable at 25°C. The TETTEX PD measurement bridge has been calibrated to 10pC. * = measurement at 1,5U ₀ ** = measurement at 1,75U ₀			Date: 30/01/2015	

Elcon Megarad Operator <i>Lombardo</i>	Elcon Megarad H.V. Lab. Responsible 
--	---


IL RESPONSABILE

	H.V. LABORATORY	Report n°: 439A/15 Date: 03/02/2015 Page: 7/8

TEST 05		Impulse voltage at elevated temperature 10 impulses for each polarity																				
OK	Applied voltage		250kV																			
			Positive Polarity – 10 shots										Negative Polarity – 10 shots									
	Line:	EM 52/1	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓		
		EM 52/2	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓		
	RESULT:		No flashovers or breakdowns										No flashovers or breakdowns									
	Note: T _{amb} = 27°C, P = 785mmHg, Relative Humidity = 60% The test has been performed on each single core,												Date: 02/02/2015									

TEST 06	A.C. voltage dry withstand 30 minutes at 2,5U ₀	
OK	LINE:	EM-52/1 - EM-52/2
	Applied Voltage:	65 kV
	Testing time:	30 min
	RESULT:	No flashovers or breakdowns
	Note: The AC test has been performed on each single core with AC HV transformer.	Date: 02/02/2015

TEST 07	Examination	
OK	LINE:	EM-52/1 – EM-52/2
	RESULT:	The accessories do not show obvious signs of damage or premature aging of materials. No leakage of mastic sealants from the upper and lower ends of the terminations and by the extremities of the joints. On the no-tracking sleeves of each terminations and on the rain sheds, no signs of electrical activity are observed.
	Note:	Date: 02/02/2015

Elcon Megarad Operator <i>Lombardo</i>	Elcon Megarad H.V. Lab. Responsible 
--	--

IL RESPONSABILE

APPENDIX 1**TEST EQUIPMENT****DC TEST:**

- DC GENERATOR: AT 128

AC TEST:

- POWER SUPPLY: AT 019
- VARIAC: AT 006
- HV TRANSFORMER: AT 010
- VOLTMETER: AT 176

PARTIAL DISCHARGE MEASUREMENT:

- POWER SUPPLY: AT 019
- VARIAC: AT 006
- HV TRANSFORMER: AT 010
- VOLTMETER: AT 176
- PARTIAL DISCHARGE BRIDGE: AT 013
- OSCILLOSCOPE: AT 011
- PD CALIBRATOR: AT 017
- HV COUPLING CAPACITY: AT 101

IMPULSE TEST:

- POWER SUPPLY: AT 004
- IMPULSE GENERATOR: AT 001
- OSCILLOSCOPE: AT 160
- IMPULSE DIVIDER: AT 169 + AT 170 + AT 175

ELECTRICAL HEATING CYCLES:

- POWER SUPPLY: AT 146
- VARIAC: AT 152
- HV TRANSFORMER: AT 148
- VOLTMETER: AT 176
- CURRENT GENERATOR: AT 024 + AT 022 + AT 123
- CURRENT TRANSFORMER: AT 026
- CURRENT TRANSDUCER: AT 083
- VOLTAGE TRANSDUCER: AT 054
- AMPEROMETER: AT 045
- TERMOMETER: AT 099
- TERMOCOUPLE TYPE T: AT 184 + AT 185

**Elcon Megarad
Operator***Lombardo***Elcon Megarad
H.V. Lab. Responsible****IL RESPONSABILE**